

General Notes:

1. All materials and construction procedures within the scope of the project shall be approved by New Braunfels Utilities and comply with the current “New Braunfels Utilities Water Systems Connection/Construction Policy”.
2. Contractor shall not proceed with any pipe installation work until they obtain a copy of the plans from the Consultant or Engineer and notify NBU Water Systems Engineering at 830-608-8971 with at least two (2) working days (48 hours) notice. **WORK COMPLETED BY THE CONTRACTOR, WHICH HAS NOT RECEIVED A NOTICE TO PROCEED FROM NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING WILL BE SUBJECT TO REMOVAL AND REPLACEMENT BY AND AT THE EXPENSE OF THE CONTRACTOR.**
3. The Developer dedicates the water / wastewater mains upon completion by the Contractor and acceptance by the New Braunfels Utilities Water System. NBU will own and maintain said water / wastewater mains which are located within platted utility easements or public ROW of proposed developments. (As applicable).
4. Contractor agrees to assume sole and complete responsibility for job site conditions during the construction of the project, including safety of all persons and property. This requirement shall apply continuously and not be limited to normal working hours. The contractor shall defend, indemnify and hold the owners and the engineer and his employees, partners officers, directors, or consultants harmless from any and all liability, real or alleged, in connection with the performance of the work on this project, excepting from liability arising from sole negligence of the owner or engineer, engineer’s directors, officers, employees, or consultants.
5. Contractor to contact the engineer-of-record (EOR) for any field changes. Any revisions or changes to the approved construction plans will require additional approval by NBU in writing.
6. Contractor and / or contractor’s independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.
7. Contractor shall be responsible for restoring to its original or better condition, any damages done to existing fences, curbs, streets, driveways, landscaping and structures, and existing utilities (not adjusted on plans). Cost of Restorations, if any, shall be the contractor’s entire expense.
8. The Contractor shall avoid cutting roots larger than one inch in diameter when excavating near existing trees. Excavation in vicinity of trees shall proceed with caution.
9. Contractor shall procure all permits and licenses, pay all charges, fees and taxes and give all notices necessary and incidental to the due and lawful prosecution of the work.

10. No extra payment shall be allowed for work called for on the plans but not included on the bid schedule. This incidental work will be required and shall be included under the pay item to which it relates.
11. Contractor is responsible for removal of all waste materials upon project completion. The contractor shall not permanently place any waste materials in the 100-year flood plain without first obtaining an approved flood plain development permit.
12. The contractor shall not place any materials on the recharge zone of the Edwards aquifer without an approved water pollution abatement plan from the TCEQ 31 TAC 313.4 and 31 TAC 313.9.
13. Barricades and warning signs shall conform to the “Texas manual on uniform traffic control devices” and shall be located to provide maximum protection to the public as well as construction personnel and equipment while providing continuous traffic flow at all times during construction. The contractor is responsible for maintaining all devices during construction.
14. Contractor is required to verify project elevations. The term “match existing” shall be understood to signify both horizontal and vertical alignment.
15. The location of utilities, either underground or overhead, shown within the right of way are approximate and shall be verified by the contractor before beginning construction operations.
16. OSHA regulations prohibit operations that will bring persons or equipment within 10 feet of an energized line. Where workmen and/or equipment have to work close to an energized electrical line, the contractor shall notify the electrical power company involved and make whatever adjustments necessary to ensure the safety of those workmen.
17. It shall be the contractor’s responsibility to locate utility service lines as required for construction. Contractors shall call the One Call System for water/wastewater location.
18. Due to federal regulations Title 49, part 192 (8), Gas companies must maintain access to gas valves at all times. The contractor must protect and work around any gas valves that are in the project area.
19. The contractor is fully responsible for the traffic control and will be responsible for furnishing all traffic control devices, and flaggers. The construction methods shall be conducted to provide the least possible interference to traffic so as to permit the continuous movement of the traffic in one direction at all times. The contractor shall clean up and remove from the work area any loose material resulting from contract operations at the end of each workday.
20. Prior to ordering materials to be used in construction, contractor shall provide the engineer with four (4) copies of the source, type, gradation, material specification data and / or shop drawings, as applicable, to satisfy the requirements of the following items and all material items referred to in these listed items:
 - a. Water mains and services
 - b. Wastewater mains and services

21. Thrust blocks will not be allowed on the system without special approval. Joints will be restrained with restraining systems approved by NBU and restraint length shall be submitted to NBU at the time of plan submittal.
22. Water jetting the backfill within a street will not be permitted. Wastewater trenches subject to traffic shall conform to NBU Connection and Construction Policy Manual.
23. Where the minimum 9 foot separation distance between wastewater lines and water lines / mains cannot be maintained, the installation of wastewater lines shall be in strict accordance with 30 TAC 217.
24. Contractor and/or Contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures. The Contractor's implementation of the systems, programs and/or procedures shall provide for adequate trench excavation safety protection that complies with as a minimum, OSHA Standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA Standards governing the presence and activities of individuals working in and around trench excavation.
25. Utility Trench Compaction with street R.O.W.
 - a. All utility trench compaction test within the street pavement section shall be the responsibility of the developer's Geo-technical engineer.
 - b. Fill material shall be placed in uniform layers not to exceed twelve inches (12") loose.
 - c. Each layer of material shall be compacted as specified and tested for density and moisture in accordance with Text Methods TEX-113-E, TEX-114-E, TEX-115-E.
 - d. The number and location of required tests shall be determined by the Geo-technical Engineer and approved by the City of New Braunfels Street Inspector.
 - e. Upon completion of testing the Geo-technical Engineer shall provide the City of New Braunfels Street inspector with all testing documentation and a certification stating that the placement of fill material has been completed in accordance with the plans.