


NOTES:

- a. All residential wastewater service laterals shall be extended to the property line and meters and cleanouts shall be installed one (1) foot outside the property line. Wastewater services to lots will extend four (4) feet past the underground electric conduit if electric infrastructure is installed in the front easement.
- b. No meter boxes or cleanouts to be set in driveways or sidewalks. Any meter boxes or cleanouts set in driveways or sidewalks will be relocated at contractor's and/or developer's expense.
- c. A stake will be required at the location of the capped sewer stub.

 NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING	DRAWN BY: <i>D. A.</i>	STANDARD DRAWING:		
	APPROVED BY: <i>N. P.</i>	NARROW LOT WATER & SEWER SERVICE ALIGNMENT SCENARIO		
	DATED: <i>12/20/18</i>	SCALE: <i>N.T.S.</i>	SHEET: <i>1 OF 1</i>	DRAWING NO. <i>410</i>